



1) DETECTABLE WARNING TAPE

NOTES:

- 1.) BEDDING MATERIAL SHALL BE CLEAN SAND OR PEA GRAVEL. OTHERWISE, NATIVE MATERIALS
 MAY BE USED PROVIDED THEY MEET PUBLIC WORKS CONSTRUCTION (GREEN BOOK) STANDARDS PER
 SUBSECTION 306.1.2.1 AND MUST HAVE A SAND EQUIVALENT OF NOT LESS THAN 30 OR HAVING A COEFFICIENT
 OF PERMEABILITY GREATER THAN 1.4 INCHES/HR.
- 2.) CONDUITS ARE DB, EB, OR SCH 40 DEPENDING ON APPLICATION PER PLAN.

7/36/19

3.) CONCRETE SHALL BE ONE SACK ENCASEMENT.

Milwy

CITY ENGINEER

NOT TO SCALE



DIVISION MANAGER DATE

PUBLIC WORKS DIRECTOR / DATE

CITY OF MORENO VALLEY

PARKS AND COMMUNITY SERVICES DEPARTMENT

TRENCH DETAILS FOR CONDUIT INSTALLATIONS IN PARKS

STANDARD PLAN

MVGF-618B-0

SHEET 2 OF 2